CANARA HIGH SCHOOL ASSOCIATION

Konkani Linguistic Minority Institution

Ammembal Subba Rao Pai Road, Kodialbail, Mangalore - 575 003

91 - 824 - 2493210 / 2496760 info@canara.ac.in www.canaraedu.org

Ref:-CHSA CE: 97/2026-2027 **Date:**-11-04-2026

To
Campus Mgr

Ref No.

To,
Sri Gajanana Machine Works,
Bunder, Mangalore-575001

Dear Sir,

Sub: Work Order for Roofing construction work (Sheet roofing, gutter installation) at New Extension block, CANARA ENGINEERING COLLEGE, Benjanapadavu.

*****

With reference to your quotation SGMW 005-26 dated 07-04-2026, we are pleased to place an order for the supply of following:

Descriptions	Quantity	MRP	Discounted MRP	Total Price	GST %	Net Price
Sheet Roofing: Providing and fabricating sheet roofing using EVEA cool sheet and single coat of epoxy paint. Sheet Area - 8345.5 sqft Materials used- • 5 x 2 sq. 3mm box tube • 2.5x 2 sq 14 gauge box tube. • 3x 1.5 14 gauge box tube. • 0.45 EVEA cool sheet (3mm thick lining).	8345.50 sqft	355/ sqft	0	2962652.50	18	3495929.95
2. Providing and fixing 6 inch UPVC Euro guard gutter	444 Rft	265/Rft	0	117660.00	18	138838.80
				Sub Total		3080312.50
				Discount		0.00
				Total		3080313.00
				GST		554456.25
				Total (Round off)		3634769.00

TERMS & CONDITIONS

- GST Included
- After Completion of work the debris & materials to be cleared immediately.
- All bills raised will be scrutinized and verified by the Project Consultant Architect Mr. Vivek Prabhu before payment.
- Bill Should be in the name of CANARA ENGINEERING COLLEGE, a unit of Canara High School Association, Mangaluru GSTN Number 29AAAAC0920C1ZF

Thanking You,

Received

HON. SECRETARY