

NO CHSA
- Project Mark.



SHRIKRISHNA. A.U

CIVIL ENGINEER & CONTRACTOR

GSTIN: 29CQHPS1307P1Z8

PAN No: CQHPS1307P

2-140 PILIGUNDA HOUSE

ARYAPU RURAL

PUTTUR, DAKSHINA KANNADA

Email: Krishnaaub@gmail.com

Mob: 9900315323

QUOTATION

95/8/2025

To

Hon SECRETARY
CANARA HIGH SCHOOL ASSOCIATION
Dongarakeri , Mangalore
GSTIN: 29AAAAC0920C1ZF

Work place- Canara engineering college, Benjanapadavu

Name of the work: Civil maintenance work at Canara engineering college, Benjanapadavu

SL. NO	DESCRIPTION	No	L	B	D	Qty.	Unit Rate	Amount
1	Removing Old cracked plastering surface. (Ceiling and wall). (approximate area)							
						2,342.00	Sft 35.00	81,970.00
2	Providing and making interior wall & ceiling plastering with CM 1:5 mix to a thickness of 12mm to 20mm to get perfect plumb finish with necessary scaffoldings, curing to the required period etc, Complete as per specification. (approximate area)							
						2,342.00	Sft 45.00	1,05,390.00
3	Removing Old Damaged wall & flooring tiles. (approximate area)							
						1,618.00	Sft 35.00	56,630.00
4	Providing and laying Vitrified tiles wall dadoing laid over 3 Star Laticrete gum and filling the joints with Epoxy joint filler including cleaning , curing etc.complete. (approximate area)							
	Wall					420.00	Sft 100.00	42,000.00
	flooring					1,198.00	Sft 120.00	1,43,760.00
5	Repairing wooden windows shutters, first clean the damaged area, then fill holes or cracks with wood filler or glue, clamp parts together if needed for stability, and finally, sand the surface smooth, removing broken glass and fixing new glass.							
	Window	28 x	5 0 x		5 0	700.00	Sft 150.00	1,05,000.00

Shrikrishna
W.O may be issued
Shrikrishna
3/19/25

Shrikrishna 25/8/25
Shrikrishna A.U. M.Tech.
Civil Engineer & Contractor
Puttur, D.K. Dist.
Mob: 9900315323

SL. NO	DESCRIPTION	No	L	B	D	Qty.	Unit Rate	Amount	
6	Taking out existing wooden door shutter, repair by cutting, painting etc. and refixing of repaired door shutters to existing door frames, including replacement of hinges with screws, etc. as required, all complete as per the direction of the Engineer-in-charge								
	Door	13 x	4	0 x	7	0	364.00 Sft	100.00	36,400.00
7	Repairing wooden desk and bench, first clean the damaged area, then fill holes or cracks with wood filler or glue, clamp parts together if needed for stability, and finally, sand the surface smooth.								
							68.00 No's	1,600.00	1,08,800.00
8	Cleaning sub surface drains including removing of dirt dust etc., using suitable soap powder, coconut broomstick, squeezers / wipers/ rubber brushes, coir brushes, plastic brushjes, mugs, booster pumps with portable arrangement, hose pipe etc., comple								
								L S	20,000.00
9	Cleaning and washing of terrace, chajja surface with soap, soda and water including cost of materials, labour, complete as per specifications.								
								L S	50,000.00
10	Painting (approximate)								
								L S	2,80,000.00
11	Reset interlock pavers, remove damaged or sunken pavers, then inspect and level the underlying base material by adding or compacting sand and gravel as needed. Clean the pavers, place them back in the correct pattern.								
							736.00 Sft	23.00	16,928.00
12	Debris Clearances.								
								L S	44,000.00
								Total	10,90,878.00
								Say	10,90,000.00

Shrikrishna 25/8/25
Shrikrishna A.U. M.Tech.
Civil Engineer & Contractor
Puttur, D.K. Dist.
Mob: 9900315323