

- WO CHSA  
- Project Mautmed



**SHRIKRISHNA. A.U**

CIVIL ENGINEER & CONTRACTOR

GSTIN: 29CQHPS1307P1Z8

PAN No: CQHPS1307P

2-140 PILIGUNDA HOUSE

ARYAPU RURAL

PUTTUR, DAKSHINA KANNADA

Email: Krishnaaub@gmail.com

Mob: 9900315323

**QUOTATION**

95/8/2025

To

Hon SECRETARY  
CANARA HIGH SCHOOL ASSOCIATION  
Dongarakeri , Mangalore  
GSTIN: 29AAAAC0920C1ZF

**Work place-** Canara engineering college, Benjanapadavu

**Name of the work:** Civil maintenance work at Canara engineering college, Benjanapadavu

| SL. NO | DESCRIPTION  | No      | L     | B     | D | Qty.            | Unit Rate    | Amount      |
|--------|--|---------|-------|-------|---|-----------------|--------------|-------------|
| 1      | Earth work in surface excavation by mechanical means for lowering & leveling the ground without blasting for all works   |         |       |       |   |                 |              |             |
|        | excavator  |         |       |       |   | 105.00          | H's 1,200.00 | 1,26,000.00 |
|        | tipper truck   |         |       |       |   | 105.00          | H's 800.00   | 84,000.00   |
|        | Rock Breaker Machine   |         |       |       |   | 72.00           | H's 1,600.00 | 1,15,200.00 |
| 2      | Earth work excavation for foundation up to a depth of 1.5 metres with initial lift and lead of excavated soil to a distance less than 15 metres. Complete as per specification.  |         |       |       |   |                 |              |             |
|        | Compond wall   | 1 x 302 | 0 x 1 | 6 x 2 | 0 | 906.00          |              |             |
|        |  |         |       |       |   | <b>906.00</b>   | Cft 20.00    | 18,120.00   |
| 3      | Providing and laying laterite in CM 1:6 mix with approved quality of laterite stone to the required sizes including necessary scaffolding, lead and lift charges curing to the required period etc. Complete as per specification.                       |         |       |       |   |                 |              |             |
|        | Foundation   |         |       |       |   |                 |              |             |
|        | Compond wall   | 1 x 302 | 0 x 1 | 0 x 1 | 8 | 503.33          |              |             |
|        | basement   |         |       |       |   |                 |              |             |
|        | Wall   | 1 x 302 | 0 x 1 | 0 x 2 | 6 | 755.00          |              |             |
|        |  |         |       |       |   | <b>1,258.33</b> | Cft 120.00   | 1,51,000.00 |
| 4      | Providing and laying I Class Masonry laterite stone in CM 1:6 mix with approved quality of laterite stone to the required sizes including necessary scaffolding, lead and lift charges curing to the required period etc. Complete as per specification. |         |       |       |   |                 |              |             |
|        | Wall   |         |       |       |   |                 |              |             |
|        |  | 1 x 302 | 0 x 0 | 9 x 5 | 0 | 1,132.50        |              |             |
|        | column   | 30 x 1  | 6 x 1 | 6 x 5 | 0 | 337.50          |              |             |
|        | Net Qty...   |         |       |       |   | <b>1,470.00</b> | Cft 135.00   | 1,98,450.00 |

1

W.O. may be issued  
3.9.25

Shrikrishna A.U. M.Tech.  
Civil Engineer & Contractor  
Puttur, D.K. Dist.  
Mob: 9900315323

| SL. NO | DESCRIPTION   | No   | L   | B   | D | Qty. | Unit Rate       | Amount                |
|--------|---|------|-----|-----|---|------|-----------------|-----------------------|
| 5      | Earth filling with available (excavated) soil from within 50 feet for footing and basement including watering, mixing consolidation, levelling etc. Complete as per specification.  |      |     |     |   |      | LS              | 30,000.00             |
| 6      | Providing and making interior wall plastering with CM 1:5 mix to a thickness of 12mm to 20mm to get perfect plumb finish with necessary scaffoldings, curing to the required period etc, Complete as per specification. <b>(approximate area)</b> |      |     |     |   |      |                 |                       |
|        |   | 2 x  | 302 | 0 x |   | 5 0  | 3,020.00        |                       |
|        | copping   | 1 x  | 302 | 0 x |   | 1 1  | 327.17          |                       |
|        | column  | 30 x | 2   | 8 x |   | 5 0  | 400.00          |                       |
|        | Net Qty   |      |     |     |   |      | <b>3,747.17</b> | Sft 45.00 1,68,622.50 |
| 7      | Painting (approximate area)   |      |     |     |   |      | <b>3,747.17</b> | Sft 25.00 93,679.17   |
| 8      | Debris Clearances.  |      |     |     |   |      | LS              | 40,000.00             |
|        |   |      |     |     |   |      | Total           | <b>10,25,071.67</b>   |
|        |   |      |     |     |   |      | Say             | <b>10,25,000.00</b>   |

*Shrikrishna 25/8/25*

**Shrikrishna A.U. M.Tech.**  
**Civil Engineer & Contractor**  
**Puttur, D.K. Dist.**  
**Mob: 9900315323**